

## **PAY ITEM NOTES**

1. PERMITS PAY ITEM SHALL INCLUDE THE COSTS OF AND EFFORTS REQUIRED TO SECURE ANY PERMITS NECESSARY FOR THE SPECIFIED DEMOLITION AND/OR CONSTRUCTION WHICH HAVE NOT BEEN PROVIDED BY THE COUNTY. SAID PERMITS MAY INCLUDE, BUT NOT NECESSARILY BE LIMITED TO DEWATERING, NPDES, DEMOLITION, AND BUILDING PERMITS.
2. MAINTENANCE OF TRAFFIC PAY ITEM SHALL INCLUDE ALL ITEMS NECESSARY TO PROVIDE A SAFE WORK ZONE AND SHOULD INCLUDE ALL NECESSARY ITEMS REQUIRED FOR THE DEVELOPMENT OF TRAFFIC CONTROL PLANS, ADDRESSING FDOT AND/OR COUNTY COMMENTS, AND ANY OTHER ITEMS NECESSARY FOR INSTALLATION AND OPERATION OF THE TRAFFIC CONTROL. THE MAINTENANCE OF TRAFFIC SHALL MAINTAIN RESIDENTIAL AND BUSINESS ACCESS DURING CONSTRUCTION WHICH MAY INCLUDE TEMPORARY PAVEMENT.
3. CLEARING AND GRUBBING PAY ITEM SHALL INCLUDE ALL ITEMS AND/OR EFFORTS NECESSARY TO REMOVE TREES, SHRUBS, GRASS, AND OTHER VEGETATION, EXISTING ABOVE GRADE AND BELOW GRADE IMPROVEMENTS, PILINGS, DOCKS, CHANNEL MARKER, BUILDINGS, OR OBSTRUCTIONS, AS REQUIRED AND/OR SPECIFIED, TO PERMIT INSTALLATION OF NEW CONSTRUCTION. HAULING AND DISPOSAL OF CLEARING AND GRUBBING DEBRIS SHALL BE INCLUDED IN THIS PAY ITEM AND SHALL BE PERFORMED IN ACCORDANCE WITH ALL LOCAL, STATE AND FEDERAL REQUIREMENTS. BIDDERS ARE DIRECTED TO REVIEW THE PRE-DEMOLITION ASBESTOS SURVEY INCLUDED WITH THE BID DOCUMENTS. CONTRACTOR SHALL COMPLY WITH ALL LOCAL, STATE AND FEDERAL REQUIREMENTS REGARDING HANDLING, TRANSPORTING, AND DISPOSAL OF HAZARDOUS MATERIALS, AS NECESSARY.
4. EROSION CONTROL PAY ITEM SHALL INCLUDE ALL ITEMS, INSPECTIONS, AND/OR EFFORTS NECESSARY TO COMPLY WITH NPDES REQUIREMENTS, PREVENT SOILS TRACKING AND EROSION, AND MAINTAIN SEDIMENT ON SITE AT ALL TIMES THROUGHOUT CONSTRUCTION AND UNTIL FINAL STABILIZATION OF THE SITE. BIDDERS ARE REMINDED THAT THE EROSION CONTROL MEASURES SHOWN IN THE PLANS ARE CONSIDERED THE MINIMUM INSTALLATION REQUIREMENT, BUT THAT ADDITIONAL EROSION CONTROL MEASURES/WORK EFFORTS AS NECESSARY ARE TO BE PROVIDED TO MAINTAIN COMPLIANCE WITH NPDES PERMIT CONDITIONS AND STATE OF FLORIDA SURFACE WATER QUALITY STANDARDS.
5. DEWATERING AND TEMPORARY SHEET PILES AT RAMPS LINE ITEM SHALL INCLUDE ALL MATERIALS AND EFFORTS NECESSARY TO INSTALL A TEMPORARY SHEET PILE COFFER DAM AND PERFORM CONTINUOUS DEWATER IN ORDER TO PROVIDE A DRY WORK AREA FOR CONSTRUCTION OF THE BOAT RAMP AND PIERS PER THE APPROVED PLANS AND PERMITS. THIS LINE ITEM SHALL ALSO INCLUDE REMOVAL OF THE TEMPORARY SHEET PILES AFTER COMPLETION OF CONSTRUCTION EFFORTS RELATED TO THE BOAT RAMP AND PIERS.

6. CHANNEL MARKERS PAY ITEM SHALL INCLUDE PROVIDING AND INSTALLATION OF 12" TIMBER PILES, AND DAYMARKERS AS INDICIATED IN PLANS AND DETAILS.
7. CHANNEL DREDGING AND SPOILS DISPOSAL PAY ITEM SHALL INCLUDE ALL ITEMS AND/OR EFFORTS NECESSARY TO COMPLETE THE HYDRAULIC DREDGING OF THE PROPOSED CHANNEL INCLUDING MOBILIZATION/DEMobilIZATION, EXCAVATION AND EARTHWORK FOR CREATION OF THE PROPOSED SPOILS BASIN, GEOTUBES, SPOILS BASIN CONTROL STRUCTURE AND DISCHARGE PIPING, FLOATING TURBIDITY BARRIERS NECESSARY TO MAINTING COMPLIANCE WITH WATER QUALITY STANDARDS AND REQUIREMENTS INDICATED IN THE APPROVED PLANS AND PERMITS, AND FINAL GRADING OF THE SPOILS PLACEMENT AREA. THIS TASK SHALL ALSO INCLUDE PROVIDING A POST-DREDGING BATHYMETRIC SURVEY TO VERIFY THAT SPECIFIED CHANNEL WIDTHS AND DEPTHS HAVE BEEN ACHIEVED.
8. PRIMITIVE CAMPING PLATFORMS PAY ITEM SHALL INCLUDE ALL EFFORTS, MATERIALS, FASTNERS, EARTHWORK AND SELECTIVE CLEARING NECESSARY TO COMPLETE THE CONSTRUCTION OF THE THREE (3) PRIMITIVE CAMPING PLATFORMS IN ACCORDANCE WITH THE APPROVED PLANS.
9. ALL STRIPING AND PAVEMENT MARKINGS SHALL BE THERMOPLASTIC.
10. ANY EARTHWORK SHALL BE INCLUDED IN THE ASSOCIATED PAY ITEM OR CONSTRUCTION ACTIVITY.
11. DEWATERING SHALL BE INCLUDED IN THE ASSOCITED PAY ITEM OR CONSTRUCTION ACTIVITY REQUIRING IT, WITH THE EXCEPTION OF THE BOAT RAMP.